

**Gilson Engineering Sales Inc.** 

Q & A for Banner DX 80 Wireless Units

First of all make sure all connections are made and power is to the units by the LED indicating lights on the units. If LED's are green on the front of the units proceed to the following:

Q- Units do not seem to be responding to one another

- A- Check and make sure the rotary switches are set correctly. Refer to step one on start up guide
- B- Verify communications to the Gateway by LED status of both LEDS per table in step 4 of start up
- C- Verify communications of the node(s) by the LED status of both LEDS per table in Step 4 of start up.
- D- Go to the site survey function shown on step 5 of the quick start guide. This will enable you to determine what kind of signal you are getting between the Gateway and node(s).
- E- If after determining the signal is good by the number of packets received refer to pages 38 to 43 of DX 80 product manual under data sheets for troubleshooting guide which includes tables to help determine the problem.

535 Rochester Road Pittsburgh, Pa 15237-1747 412-369-0100 Fax 412-366-1728 www.gilsoneng.com